

ITEM NUMBER	BID ITEM	DESCRIPTION	UNITS	EST. QTY	AS-BUILT QTY
General Items					
1	9.0010	Mobilization	LS	1	
2	9.0550	Tax on City Furnished Materials	LS	1	
Traffic Control					
3	634.0110	Traffic Control	SqFt	624	
4	634.0120	Traffic Control, Miscellaneous	LS	1	
5	634.0285	Type 3 Barricade, 8' Double Sided	Each	13	
6	634.1050	Temporary Business Sign	Each	2	
7	634.1215	Contractor Furnished Portable Changeable Message Sign	Each	2	
8	999.0023	Temporary Mailbox	Each	17	
9	Special	Temporary Gravel Access	LS	1	
10	Special	Winter Maintenance	LS	1	
Erosion Control, Planting & Landscaping					
11	700.0210	Class B Riprap	Ton	775	
12	730.0100	Cover Crop Seeding	Bu	0.2	
13	730.0302	Wetland Seed Mixture 2	Lb	160	
14	731.0200	Weed Control	SqYd	20926	
15	731.0210	Weed Control - Project	LS	1	
16	731.0100	Fertilizing	Lb	1221	
17	732.0300	Bonded Fiber Matrix	Ton	7.3	
18	732.0400	Soil Stabilizer	Acre	4.2	
19	734.0105	Erosion Control Blanket	SqYd	6537	
20	734.0154	12" Diameter Erosion Control Wattle	Ft	50	
21	734.0175	Temporary Sediment Basin	Each	1	
22	734.0601	Silt Fence	Ft	2333	
23	734.0610	Mucking Silt Fence	CuYd	162	
24	734.0620	Repair Silt Fence	Ft	583	
25	734.0850	Type B Inlet Protection	Each	2	
26	734.0855	Silt Fence Drop Inlet Sediment Filter	Each	22	
27	734.5010	Sweeping	Hour	10	
28	734.6001	Temporary Vehicle Tracking Control	Each	2	
29	734.6006	Concrete Washout Area	Each	1	
30	831.0110	Type B Drainage Fabric	SqYd	556	
Removals					
31	999.0021	Remove and Reset Mailbox and Post	Each	17	
32	100.0020	Clear and Grub Tree	Each	65	
33	100.0100	Clearing	LS	1	
34	110.0130	Remove Traffic Sign	Each	4	
35	110.0300	Remove Concrete Curb and Gutter	Ft	220	
36	110.0510	Remove Pipe End Section	Each	1	
37	110.0530	Remove Storm Sewer Pipe	Ft	368	
38	110.0600	Remove Fence	Ft	1285	
39	110.1010	Remove Asphalt Concrete Pavement	SqYd	4135	
40	110.1100	Remove Concrete Pavement	SqYd	6	
41	110.1700	Remove Silt Fence	Ft	583	
42	110.1970	Remove Water Main	Ft	20	
43	110.5021	Salvage Traffic Sign for Reset	Each	8	
44	110.5780	Salvage Valve	Each	1	
45	110.5770	Salvage Valve Box	Each	1	
46	110.7510	Remove Pipe End Section for Reset (18" RCP)	Each	1	
47	110.7510	Remove Pipe End Section for Reset (24" RCP)	Each	1	
48	110.8100	Saw Existing Asphalt	Ft	47	
49	110.8110	Saw Existing PCC Pavement	Ft	22	
Grading					
50	120.0100	Unclassified Excavation, Digouts	CuYd	1500	
51	230.0010	Placing Topsoil	CuYd	4389	
52	230.0300	Salvage Topsoil	CuYd	9480	
53	250.0020	Incidental Work, Grading	LS	1	
Storm Sewer					
54	450.0114	15" RCP Class 4, Furnish	Ft	27	
55	450.0120	15" RCP, Install	Ft	27	
56	450.0123	18" RCP Class 3, Furnish	Ft	652	
57	450.0130	18" RCP, Install	Ft	652	
58	450.0143	24" RCP Class 3, Furnish	Ft	1920	
59	450.0150	24" RCP, Install	Ft	1920	
60	450.0163	30" RCP Class 3, Furnish	Ft	1016	
61	450.0170	30" RCP, Install	Ft	1016	
62	450.0183	36" RCP Class 3, Furnish	Ft	74	
63	450.0190	36" RCP, Install	Ft	74	
64	450.2008	18" RCP Flared End, Furnish	Each	3	
65	450.2009	18" RCP Flared End, Install	Each	3	

ITEM NUMBER	BID ITEM	DESCRIPTION	UNITS	EST. QTY	AS-BUILT QTY
Storm Sewer					
66	450.2016	24" RCP Flared End, Furnish	Each	2	
67	450.2017	24" RCP Flared End, Install	Each	2	
68	450.2028	36" RCP Flared End, Furnish	Each	1	
69	450.2029	36" RCP Flared End, Install	Each	1	
70	450.3053	48" RCP Arch Class 3, Furnish	Ft	384	
71	450.3060	48" RCP Arch, Install	Ft	384	
72	450.4520	48" RCP Arch Flared End, Furnish	Each	6	
73	450.4521	48" RCP Arch Flared End, Install	Each	6	
74	450.9001	Reset Pipe End Section	Each	2	
75	462.0100	Class M6 Concrete	CuYd	69	
76	480.0100	Reinforcing Steel	Lb	12355	
77	670.1100	Type Y Manhole Frame and Lid	Each	2	
78	670.1210	Type B Frame and Grate Assembly - Left Flange	Each	20	
79	670.1230	Type B Frame and Grate Assembly - Right Flange	Each	20	
80	670.1300	Type Area Inlet Frame and Grate Assembly	Each	2	
81	670.1400	Frame and Cover-Type 1 Junction Box	Each	9	
82	680.0660	6" Slotted Corrugated Polyethylene Drainage Tubing	Ft	8844	
83	Special	Detention Pond Outlet Structure	Each	1	
84	Special	6" PVC Storm Sewer Pipe	Ft	20	
85	Special	Connect to Existing Drain Tile	Each	1	
Water Main					
86	110.1912	Remove & Relocate Fire Hydrant	Each	1	
87	250.0040	Incidental Work, Utilities	LS	1	
88	260.7010	Trench Stabilization Material	Ton	500	
89	260.7020	Select Fill	Ton	100	
90	Special	Install City Furnished 6" C900 DR 18 PVC Water Main	Ft	141	
91	900.0202	8" C900 DR 18 PVC Water Main	Ft	77	
92	Special	Install City Furnished 12" C900 DR 18 PVC Water Main	Ft	128	
93	900.0205	16" C900 DR 18 PVC Water Main	Ft	2286	
94	900.0301	6" Restrained Joint PVC Pipe	Ft	46	
95	900.0302	8" Restrained Joint PVC Pipe	Ft	57	
96	900.0304	12" Restrained Joint PVC Pipe	Ft	282	
97	Special	16" Restrained Joint PVC Pipe	Ft	524	
98	Special	Install City Furnished Valve Box	Each	1	
99	Special	Install Salvaged Valve/Valve Box	Each	1	
100	Special	Install City Furnished 6" MJ Gate Valve with Box	Each	3	
101	Special	Install City Furnished 8" MJ Gate Valve with Box	Each	5	
102	Special	Install City Furnished 12" MJ Gate Valve with Box	Each	7	
103	Special	16" MJ Gate Valve with Box	Each	4	
104	Special	Install City Furnished 6" MJ Elbow 11.25/22.5/45 Degree	Each	4	
105	Special	Install City Furnished 8" MJ Elbow 11.25/22.5/45 Degree	Each	6	
106	900.0504	12" MJ Elbow 11.25/22.5/45 Degree	Each	12	
107	Special	Install City Furnished 6" MJ Elbow 90 Degree	Each	3	
108	Special	Install City Furnished 12" x 6" MJ Tee	Each	4	
109	Special	Install City Furnished 16" x 8" MJ Tee	Each	5	
110	Special	Install City Furnished 8"x8" MJ Reducer	Each	5	
111	Special	Install City Furnished 16"x6" MJ Reducer	Each	1	
112	900.0917	16" x 12" MJ Cross	Each	3	
113	900.1004	12" MJ Plug	Each	4	
114	900.1104	12" MJ Cap	Each	3	
115	Special	Install City Furnished 12" MJ Long Sleeve	Each	1	
116	Special	Install City Furnished 16" MJ Long Sleeve	Each	1	
117	Special	Install City Furnished 6" M.J. Retainer Gland	Each	43	
118	Special	Install City Furnished 8" M.J. Retainer Gland	Each	32	
119	Special	Install City Furnished 12" M.J. Retainer Gland	Each	53	
120	Special	Install City Furnished 16" M.J. Retainer Gland	Each	27	
121	Special	Install City Furnished Fire Hydrant	Each	10	
122	900.1701	6" Water Main Adjustment	Each	1	
123	900.1702	8" Water Main Adjustment	Each	1	
124	900.1704	12" Water Main Adjustment	Each	3	
125	900.1750	Connect to Existing Water Main	Each	3	
126	900.1905	16" C900 DR 18 PVC Water Main - Extra Depth	Ft	41	
127	900.3110	6" x 1-1/2" Water Service Tap	Each	1	
128	900.3130	8" x 1-1/2" Water Service Tap	Each	4	
129	900.3220	1-1/2" Water Service Curb Stop	Each	5	
130	900.3520	1-1/2" PEXa Water Service Piping	Ft	311	
131	900.4000	Water Main Insulation	Ft	16	
132	900.6250	Valve Box Marker	Each	2	
133	900.8001	6" Water Main Bedding Material	Ft	187	
134	900.8002	8" Water Main Bedding Material	Ft	134	

ITEM NUMBER	BID ITEM	DESCRIPTION	UNITS	EST. QTY	AS-BUILT QTY
Water Main (Ctd.)					
135	900.8004	12" Water Main Bedding Material	Ft	410	
136	900.8005	16" Water Main Bedding Material	Ft	2851	
137	950.5200	Trench Dewatering	LS	1	
138	950.5700	Locating Utility	Each	10	
139	950.5710	Verify Utility	Each	13	
140	975.1100	Casing Pipe (12" Steel)	Ft	20	
141	975.1100	Casing Pipe (16" Steel)	Ft	20	
142	975.1100	Casing Pipe (20" Steel)	Ft	60	
143	975.1100	Casing Pipe (24" Steel)	Ft	200	
144	975.1200	Carrier Pipe (6" Restrained Joint PVC Pipe)	Ft	20	
145	975.1200	Carrier Pipe (8" Restrained Joint PVC Pipe)	Ft	20	
146	975.1200	Carrier Pipe (12" Restrained Joint PVC Pipe)	Ft	60	
147	975.1200	Carrier Pipe (16" Restrained Joint PVC Pipe)	Ft	200	
148	Special	Cathodic Protection	LS	1	
Traffic Signals					
149	250.0016	Incidental Work, Traffic	LS	1	
150	635.1110	1" Innerduct, SDR 13.5	Ft	8640	
151	635.4212	12" Diameter Junction Box	Each	12	
152	635.4224	24" Diameter Junction Box	Each	13	
153	635.4230	30" Diameter Junction Box	Each	16	
154	635.4610	Tie To Existing Junction Box	Each	1	
155	635.6900	Locator Ball	Each	6	
156	635.8010	1" Rigid Conduit, Schedule 40	Ft	360	
157	635.8020	2" Rigid Conduit, Schedule 40	Ft	180	
158	635.8120	2" Rigid Conduit, Schedule 80	Ft	715	
159	635.8130	3" Rigid Conduit, Schedule 80	Ft	2515	
160	635.8455	1/C #12 AWG Copper Wire	Ft	6700	
Lighting					
161	250.0015	Incidental Work, Lighting	LS	1	
162	635.4218	18" Diameter Junction Box	Each	10	
163	635.4224	24" Diameter Junction Box	Each	2	
164	635.4230	30" Diameter Junction Box	Each	1	
165	635.4510	Power Feed - Elevated Transformer to Double Meter Pedestal	Each	2	
166	635.4600	Tie To Existing Conduit	Each	1	
167	635.4630	Tie To Existing Luminaire Pole Base	Each	1	
168	635.6900	Locator Ball	Each	4	
169	635.8020	2" Rigid Conduit, Schedule 40	Ft	3090	
170	635.8120	2" Rigid Conduit, Schedule 80	Ft	2505	
171	635.8460	1/C #14 AWG Copper Wire	Ft	5890	
Surfacing					
172	120.6200	Water for Granular Material	Mgal	387	
173	260.3010	Gravel Surfacing	Ton	210	
Alternate A - Geotextile Fabric and Subbase					
A1	120.0010	Unclassified Excavation	CuYd	49688	
A2	120.0150	Unclassified Excavation, Grade Stabilization	CuYd	1500	
A3	120.0480	Scarify and Recompact Subgrade	SqYd	18130	
A4	260.0010	Subbase	Ton	11024	
A5	260.1010	Aggregate Base Course	Ton	32030	
A6	831.0050	Geotextile Fabric For Subgrade Stabilization	SqYd	36300	
Alternate B - Cement Stabilized Subgrade					
B1	120.0010	Unclassified Excavation	CuYd	44368	
B2	120.8000	Cement Stabilized Subgrade	SqYd	36300	
B3	120.8010	Type I or II Cement	Ton	1040	
B4	260.1010	Aggregate Base Course	Ton	16915	



Tallgrass Avenue Grading and Utility Improvements
85th Street to South Veterans Parkway
Sioux Falls, South Dakota

Estimate of Quantities

REVISIONS

Project Manager: SSL
Designer: MLP
Project Number: 671129
Phone: (605) 339-4157

CITY OF SIOUX FALLS
PUBLIC WORKS
Providing a Better Quality of Life for You!



Sheet

B1