

ESTIMATE OF QUANTITIES

ITEM NO.	STD BID NO.	ITEM DESCRIPTION	UNIT	APPROX. QUANTITY
		General/Traffic Control		
1	9.0010	Mobilization	LS	1
2	634.0110	Traffic Control	SqFt	149
3	634.0120	Traffic Control, Miscellaneous	LS	1
4	634.0285	Type 3 Barricade, 8' Double Sided	Each	12
		Removals		
5	110.0300	Remove Concrete Curb and Gutter	Ft	540
6	110.0520	Remove Sewer Pipe	Ft	24
7	110.0525	Abandon Sanitary Sewer Pipe	Ft	426
8	110.1010	Remove Asphalt Concrete Pavement	SqYd	791
9	110.1110	Remove Concrete Approach Pavement	SqYd	26
10	110.1461	Remove Sanitary Sewer Manhole	Each	2
11	110.0530	Remove Storm Sewer Pipe	Ft	6
12	110.1970	Remove Watermain	Ft	5
13	110.8100	Saw Existing Asphalt	LFt	479
14	110.8110	Saw Existing PCC Concrete	LFt	12.5
		Grading		
15	120.0010	Unclassified Excavation	CuYd	133
16	230.0300	Salvage Topsoil	CuYd	199
17	230.0010	Place Topsoil	CuYd	199
18	120.0100	Unclassified Excavation, Digouts	CuYd	20
19	120.0480	Scarify and Recompact Subgrade	SqYd	553
		Erosion Control/Restoration		
20	120.6300	Water For Vegetation	MGal	92.88
21	230.0020	Placing Contractor Furnished Topsoil	CuYd	258
22	730.0252	Special Permanent Seed Mixture 2	Lb	10.65
23	730.0301	Quality Green Turf Mix	Lb	19.24
24	731.0100	Fertilizing	Lb	80
25	731.0200	Weed Control	SqYd	1548
26	731.0210	Weed Control - Project	LS	1
27	Special	Remove & Reset Landscaping	SqYd	26
28	Special	Salvage and Reset Plant	Each	5
29	732.0200	Fiber Mulch	Ton	0.32
30	734.0850	Inlet Protection	Each	3
31	734.5010	Sweeping	Hour	10
32	734.6001	Temporary Vehicle Tracking Control	Each	1
33	736.6006	Concrete Washout Area	Each	1

ITEM NO.	STD BID NO.	ITEM DESCRIPTION	UNIT	APPROX. QUANTITY
		Surfacing		
34	120.6200	Water For Granular Material	MGal	6.3
35	260.1010	Aggregate Base Course	Ton	527
36	320.1210	Asphalt Concrete Composite, PG58-28	Ton	121
37	320.1250	Asphalt Concrete For Patching	Ton	85
38	380.3520	6" PCC Approach Pavement	SqYd	26
39	831.0050	Geotextile Fabric For Subgrade Stabilization	SqYd	553
40	380.6110	Insert Steel Bar in PCC Pavement	Each	10
41	650.7000	Concrete Curb & Gutter Type SF66	Ft	540
		Watermain		
42	975.1000	Trenchless Construction	Ft	244
43	975.1310	Bore Obstruction-Surface Excavation	Each	2
44	900.0201	6" C900 DR18 PVC Watermain	Ft	14
45	900.0202	8" C900 DR18 PVC Watermain	Ft	85
46	900.0302	8" Restrained Joint PVC Pipe	Each	244
47	900.0403	8" MJ Gate Valve With Box	Each	1
48	900.0502	8" MJ Elbow 45 Degree	Each	4
49	900.0701	6" X 6" MJ Tee	Each	1
50	900.0802	8" X 6" MJ Reducer	Each	1
51	900.0805	10" X 8" MJ Reducer	Each	1
52	900.1201	6" MJ Long Sleeve	Each	1
53	900.1202	8" MJ Long Sleeve	Each	1
54	900.1401	6" MJ Retainer Gland	Each	8
55	900.1402	8" MJ Retainer Gland	Each	13
56	900.1403	10" MJ Retainer Gland	Eatch	1
57	975.1100	Casing Pipe (16" C905)	Ft	12
58	900.1702	8" Watermain Adjustment	Each	1
59	900.1750	Connect To Existing Watermain	Each	1
60	900.1751	Cut and Tie To Existing Watermain	Each	2
61	900.8001	6" Watermain Bedding Material	Ft	14
62	900.8002	8" Watermain Bedding Material	Ft	85

FOR BIDDING PURPOSES ONLY



ESTIMATE OF QUANTITIES

ITEM NO.	STD BID NO.	ITEM DESCRIPTION	UNIT	APPROX. QUANTITY
		Sanitary Sewer		
63	260.7010	Trench Stabilization Material	Ton	100
64	950.0100	8" Sanitary Sewer Pipe 0' To 6' Deep	Ft	133
65	950.0101	8" Sanitary Sewer Pipe 6' To 8' Deep	Ft	269
66	950.0201	10" Sanitary Sewer Pipe 6' To 8" Deep	Ft	6
67	950.3103	10" Sewer Coupling	Each	1
68	950.2001	10" Sanitary Sewer Pipe Bedding Material	Ft	6
69	950.2000	8" Sanitary Sewer Pipe Bedding Material	Ft	402
70	950.3003	8" X 6" Sewer Wye/Tap	Each	3
71	950.4000	48" Manhole 0' - 6' Deep	Each	1
72	950.4001	48" Manhole 6' - 8' Deep	Each	1
73	950.4003	10" Boots For Manhole	Each	2
74	950.4802	8" Boots For Manhole	Each	2
75	950.4910	Reconnect Sewer Service	Each	3
76	950.4851	6" Sanitary Sewer Service	Ft	86
77	950.5001	Adjust Manhole - Asphalt Streets	Each	1
78	950.5300	Manhole Frame and Cover	Each	1
79	950.5310	Manhole Frame with Bolt Down Cover Plate	Each	1
80	950.5320	Manhole External Frame Seal	Each	1
81	950.5410	Manhole Construction Plate Marker	Each	2
82	950.5500	Sanitary Sewer Pipe Insulation	Ft	161
83	950.5600	Manhole Exfiltration/Vacuum Test	Each	2
84	950.5610	Sanitary Sewer Exfiltration Testing	Ft	402
85	950.5620	PVC Sewer Pipe Deflection Test	Ft	402
86	950.5700	Locating Utility	Each	20
87	950.5710	Verify Utility	Each	3
		Storm Sewer		
88	450.0105	12" RCP Class 5, Furnish	Ft	37
89	450.0110	12" RCP, Install	Ft	37
90	462.0100	Class M6 Concrete	CuYd	3.96
91	480.0100	Reinforcing Steel	Lb	500
92	670.1200	Type B Frame and Assembly	Each	1
93	670.1100	Type Y Manhole Frame and Lid	Each	1

FOR BIDDING PURPOSES ONLY

